

Schedule Two

Public Facility Fee (PFF) Removed Facilities

Item	Description	Project Scope	Total Cost	Reimb	City Expenditures	Remaining Cost
Bridges:						
B10	Natomas Crossing Drive Over West Drain Canal	Four (4) lane bridge, 74 ft wide by 80 ft length. Bridge to include (4) 12' lanes, (2) 6' bike lanes and, (2) 5' sidewalks and a 4' painted median.	\$ -			\$ -
Road Segments:						
17	Natomas Crossing Drive	Roadway Segment 17 from Duckhorn Drive to El Centro Road. A two (2) lane roadway segment. Roadway segment length of 4,180 feet; roadway width of 70 feet. City landscape quality level "B". Roadway section type "A".	\$ -			\$ -
Fully Funded Signals:						
4-Lane x 4-Lane						
10	El Centro Road and Natomas Crossing Drive	Traffic signal at a 4-Lane x 4-Lane intersection.	\$ -			\$ -
Overcrossings:						
	Snowy Egret Way	A 4 lane, 85 ft wide overcrossing over Interstate 5 to include approaches from East Commerce Way to El Centro Road. This overcrossing assumes an 85' right of way with (4) 12' lanes, 12' striped median, (2) 6' bike lanes/shoulders and (2) 6' sidewalks with barriers.	\$ -			\$ -